## **ROADWAY SUMMARY** (PAGE 1 OF 1)

## PINETREE LANE

L.M.I.G. City of Auburn

From: Greentree Drive To: Dead End at Cul-de-sac

340 Lin. Ft. 0.06 Mile

20' Wide Pavement (no curb & gutter)21' Wide Full Depth Reclamation (6" wider each side of new pavement edge)

<u>ITEM</u>	UNIT OF MEASURE	APPROX. QUANTITY
Full Depth Reclamation with Portland Cement, Including pulverization/recycling of existing soil/crushed stone base and existing asphalt pavement materials. Recycle depth to be 8" inches. Reconstruction to include reshaping, grading, proper compaction and curing. 40 lbs/yd2 of Portland Cement to be used. Bituminous Prime Coat included.	SQUARE YARD	1,260
Recycled Asphaltic Concrete 12.5 MM Superpave wearing course, Blend 1, Including Bituminous Material, Hydrated Lime & Haul. 220 lbs/yd2.	TON	150
Bituminous Tack Coat	GALLONS	90
Solid Traffic Stripe, 24" (inch), White, Standard Thermoplastic	LINEAR FOOT	10
Shoulder Re-Construction & Turf Establishment	SHOULDER MILE	0.15
Traffic Control	LUMP	100 %
Asphaltic Concrete Testing (To include Asphaltic Concrete Core Samples)	ЕАСН	1