

**ROADWAY SUMMARY
(PAGE 1 OF 1)**

POINTERS WAY (cul-de-sac only – east of Hunters Cove)

City of Auburn

NON – L.M.I.G.

From: 250' feet east of Hunters Cove

To: dead end cul-de-sac

Square Yards: 580

No Curb & Gutter

Remove & Replace Cul-de-Sac Asphalt

<u>ITEM</u>	<u>UNIT OF MEASURE</u>	<u>APPROX. QUANTITY</u>
Recycled Asphaltic Concrete, 19 MM Superpave, Group 1 or 2, including Bituminous Material, Hydrated Lime & Haul, 220 lbs/yd ² .	TON	65
Recycled Asphaltic Concrete, 12.5 MM Superpave, Blend 1, Including Bituminous Material, Hydrated Lime & Haul. 165 lbs/yd ² .	TON	50
Mill Asphalt Concrete Existing Pavement (approximately 1 inch to 2 inches) & Set Existing Graded Aggregate Base	SQUARE YARD	580
Bituminous Tack Coat	GALLONS	35
Shoulder Re-Construction & Turf Establishment	SHOULDER MILE	0.05
Traffic Control	LUMP	100 %